

"SINCE 1923"
AAA ROOFING COMPANY, INC.
910 NORTH HIGHLAND AVENUE
INDIANAPOLIS, INDIANA 46202
PHONE: 317-635-2928 FAX: 317-685-8876

2/28/2022

Mt. Vernon Middle School
Metal Panel/Siding replacement on Penthouses

RE: Metal Panel/Siding replacement

SCOPE OF WORK: All work listed below in the summary's shall follow Moisture Management Specifications and detail drawings. (All pricing listed below would be in addition to the base bid.)

Penthouse #1: 1562 sq. ft.

1. Remove existing coping from top of wall.
2. Remove existing insulated wall panels.
3. Install all required flashing, required by McElroy Metals.
4. Install new 3" insulated wall panels, McElroy Green Span panels.
5. Install coping at top of new panels.
6. Dispose of all debris.

Current cost for Penthouse #1 amounts to \$82,800.00

Penthouse #2: 2470 sq.ft.

1. Remove existing coping from top of walls.
2. Remove existing insulated wall panels.
3. Install all required flashing, required by McElroy Metals.
4. Install new 3" insulated wall panels, McElroy Green Span panels.
5. Install coping at top of walls.
6. Dispose of all debris.

Current cost for Penthouse #2 amounts to \$123,500.00

Penthouse # 3: 1000 sq. ft.

1. Remove existing coping from top of walls.
2. Remove existing insulated wall panels.
3. Install all required flashing, required by McElroy Metals.
4. Install new 3" insulated wall panels, McElroy Green Span panels.
5. Install coping at top of walls.
6. Dispose of all debris.

Current cost for Penthouse #3 amounts to \$54,500.00

NOTE: Owner will need to remove or disconnect any equipment attached to interior wall panels.

NOTE: All metal siding and trims will be your choice of standard colors.

If you have question or concerns, please do not hesitate to call.

Thank you,

Scott Price

Operations Manager

AAA Roofing Co Inc.

O-317-635-2928

F-317-685-8876

C-317-501-9114